

OREGON ON-SITE CONCRETE, INC

26045 SW Grahams Ferry Rd.
Sherwood, OR 97140
503.218.5050

CONCRETE MIX DESIGN

MIX DESIGN ID: PDX 4000

DESIGNED BY: Andy Wallender

CUSTOMER: OOC INTERNAL
PROJECT: OOC INTERNAL
PROJECT NO.: OOC INTERNAL

WEIGHT PER CUBIC YARD

	LBS	CU.FT.
ASTM-C150 TYPE I/II CEMENT (Cal Portland)	550	2.80
#3/4-4 COARSE AGGREGATE (Windsor Rock Products)	1750	10.79
FINE AGGREGATE (Windsor Rock Products)	1356	8.48
WATER	231	3.70
AIR ENTRAINED (DARAVAIR® 1000 Air-entraining admixture ASTM C260)	1.5%	0.40
AIR ENTRAPPED	3.1%	0.83
TOTAL VOLUME		27.00

ADMIXTURES

Air Entrainment – DARAVAIR 1000

SPECIFICATIONS

WATER/CEMENT RATIO	0.42	
SLUMP	4-6	Inches
COMPRESSIVE STRENGTH @ 28 Days	4000	p.s.i.