

OREGON ON-SITE CONCRETE, INC

26045 SW Grahams Ferry Rd.
Sherwood, OR 97140
503.218.5050

CONCRETE MIX DESIGN

MIX DESIGN ID: PDX5000

DESIGNED BY: Bryan Holland

CUSTOMER: OOC INTERNAL
PROJECT: OOC INTERNAL
PROJECT NO.: OOC INTERNAL

WEIGHT PER CUBIC YARD

	LBS	CU.FT.
ASTM-C150 TYPE I/II CEMENT (Cal Portland)	600	3.05
#3/4-4 COARSE AGGREGATE (Windsor Rock Products)	1750	10.4
FINE AGGREGATE (Windsor Rock Products)	1335	7.95
WATER	290	4.65
AIR ENTRAINED (DARAVAIR® 1000 Air-entraining admixture ASTM C260)	0.0%	00.0
AIR ENTRAPPED	2.5%	0.65
TOTAL VOLUME		26.7

ADMIXTURES

Air Entrainment – DARAVAIR 1000

SPECIFICATIONS

WATER/CEMENT RATIO	0.48
SLUMP	4-6 Inches
COMPRESSIVE STRENGTH @ 28 Days	5000 p.s.i.